

ADDENDUM NO. 4

BID TITLE: Weston Road Improvements Surtax-Funded Municipal Transportation Project No. West 303

BID NO: 2025-02

DATE: May 19, 2025

To All Bidders:

Bidders for the above referenced BID shall take note of the following changes, additions, deletions, clarifications, etc., to the BID documents, which shall become a part of and have precedence over anything shown or described otherwise.

A. CHANGES IN THE BID DOCUMENTS

- 1) ARTICLE 7.0, BID AMOUNTS is hereby replaced with the attached REVISED ARTICLE 7.0, BID AMOUNTS.
- 2) VOLUME II, "Measurement and Payment" section is hereby replaced with the attached "Revised Measurement and Payment".
- 3) The "BID SUBMITAL DEADLINE" Section of Document 00010-2, Notice to Bidders, is being changed to reflect a new deadline date as follows:

SUBMITTAL DEADLINE

Bids shall be received by the Director of Procurement until **2:30 p.m. local time, on ~~May 13, 2025~~ ~~May 15, 2025~~ ~~May 22, 2025~~ **May 27, 2025**** (the "Bid Submittal Deadline") at City of Weston, City Hall, located at 17200 Royal Palm Boulevard, Weston, Florida. The official clock at the City Hall reception desk shall govern. Submittals received after this time shall be returned unopened. The sealed submittals will be publicly opened and at the City of Weston, City Hall after the Bid Submittal Deadline. Award of a bid will be made at a City Commission meeting. The public opening of submittals may be viewed by the public via the Live Event link to Cisco Webex as follows:

Event:	Opening: Bid No. 2025-02, Weston Road Improvements
Event address for attendees:	https://westonfl.webex.com/westonfl/j.php?MTID=m2a6eea739d955ed5f28773b11eecaf91
Date and time:	Tuesday, May 13, 2025 Thursday, May 15, 2025 Thursday, May 22, 2025 Tuesday, May 27, 2025 at 2:30 p.m. Eastern Standard Time (New York, GMT-05:00)
Event number:	2317 213 7500
Event password:	Weston (937866 when dialing from a phone or video system)

Audio conference:	Join by phone 415-655-0001 US Toll
	Access code: 2317 213 7500

B. CLARIFICATIONS

None.

C. QUESTIONS FROM BIDDERS

1. Q: Are there any pay items for the 94 bike and arrow bike lane signs?
A: See attached REVISED ARTICLE 7.0, BID AMOUNTS.

2. Q: The plans show electrical conductors but there are no pay items on the bid form. There is also reference to some up lights bearing a HADCO part number. There is no pay item for this (unless it is being covered under the landscaping)
A: See attached REVISED ARTICLE 7.0, BID AMOUNTS and Revised Measurement and Payment

ATTACHMENTS:

1. REVISED ARTICLE 7.0, BID AMOUNTS
2. Revised Measurement and Payment (from VOLUME II)

END OF ADDENDUM NO. 4

All other information remains as originally described in the solicitation.

REVISED ARTICLE 7.0
BID AMOUNTS

The Bidder offers the following for providing all labor, materials, equipment, and all other incidental costs to complete the project in accordance with the contract documents. The costs for each individual pay item as set out herein shall be inclusive of all costs for each. All quantities are estimated. Payment will be made only for the quantities actually used.

BID ITEM	FDOT ITEM	DESCRIPTION	QTY	UNIT	UNIT RATE PRICE	ESTIMATED AMOUNT
General Items						
1.01		Mobilization and Demobilization (maximum of 2.5% of total price)	1	LS		
1.02	0102 1	Maintenance of Traffic (maximum of 2.5% of total price)	1	LS		
1.03		Stormwater Pollution Prevention	1	LS		
1.04		Permitting Allowance	1	AL	\$10,000.00	\$10,000.00
1.05		General Items (maximum of 2.5% of total price)	1	LS		
Drainage						
2.01	0400 011	Concrete Class Ns, Gravity Wall Index 400-011	6	CY		
2.02	0425-1-341	Inlets, Curb, Type P-4, < 10'	1	EA		
2.03	0425-1-351	Inlets, Curb, Type P-5, < 10'	2	EA		
2.04	0425-1-201	Inlets, Curb, Type 9, < 10'	2	EA		
2.05	0425-1-361	Inlets, Curb, Type P-6, < 10'	3	EA		
2.06	0425-	Inlets, Curb, P-6, Offset	3	EA		
2.07	0425-11	Inlets, Modify, Partial	1	EA		
2.08	0430-982-129	Mitered End Section (Mes) 24"	1	EA		
2.09	0430-175-118	18" RCP Pipe	1510	LF		
2.10	0430-175-124	24" RCP Pipe	342	LF		
2.11	0430-001	Concrete Jacket (F&I)	1	EA		
2.12		Concrete Aprons (includes removal of existing where necessary)	13	EA		
2.13	0430-524-120	Drainage Oufall	1	EA		
Roadway/Site						
3.01	0110-1-1	Clearing and Grubbing – See Spec 01012	1	LS		
3.02	0110 21	Tree Protection Barrier	560	LF		
3.03	0110 22	Tree Root and Branch Pruning	7	EA		
3.04	0110 23	Tree Removal	1	EA		
3.05	0110 4 10	Removal of Existing Concrete	4985	SY		
3.06	0120-1-	Regular Excavation	1250	CY		
3.07	0120-4	Subsoil Excavation	105	CY		
3.08	0145 2	Geosynthetic Reinforced Foundation Over Soft Soil	3170	SY		
3.09	0160 4	Type B Stabilization	3214	SY		

BID ITEM	FDOT ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE RATE	ESTIMATED AMOUNT
Roadway/Site (continued)						
3.10	0210 2	Limerock-New Material for Reworking Base	1057	CY		
3.11	0327 70 1	Milling Existing Asphalt Pavement, 1" Avg Depth	145325	SY		
3.12	0337 7 82	Asphalt Concrete Friction Course, Traffic C, FC-9.5, Pg 76-22	8351	TN		
3.13	0519 78	Bollards	8	EA		
3.14	0520 1 10	Concrete Curb & Gutter, Type F includes Curb Pad	4480	LF		
3.15	0520-2-114	8" D Curb	1000	LF		
3.16	0527 2	Detectable Warnings	78	EA		
3.17	0552 1	Concrete Sidewalk and Driveways, 4" Thick	2816	SY		
3.18	0570 1 2	Performance Turf, Sod	2247	SY		
3.19	1080-21-500	Adjust Existing (Valves, Manholes, Pull Boxes) to Existing Grade	39	EA		
3.20	0526-1-101	Removal of Existing Pavers	55	SY		
3.21	751-35-43	Relocate/Reconstruct Existing Bus Shelter - Includes New Foundation and Paver Reconstruction See Spec. 01012	2	EA		
3.22		Irrigation System Modifications	1	LS		
Signalization						
4.01	0630 2 11	Conduit, Furnish & Install, Open Trench	310	LF		
4.02	0630 2 12	Conduit, Furnish & Install, Directional Bore	1145	LF		
4.03	0632 7 1	Signal Cable- New or Reconstructed Intersection, Furnish & Install	5	PI		
4.04	0632 7 6	Signal Cable, Remove- Intersection	5	PI		
4.05	0635 2 11	Pull & Splice Box, F&I, 13" X 24" Cover Size	36	EA		
4.06	0635 2 12	Pull & Splice Box, F&I, 24" X 36" Cover Size	2	EA		
4.07	0639 1122	Electrical Power Service F&I, underground, meter furnished by Contractor	2	AS		
4.08	0639 2 1	Electrical Service Wire, F&I	440	LF		
4.09	0439 2 12	Electrical Service Disconnect, F&I, Cabinet	2	EA		
4.10	0646 1 11	Aluminum Signals Pole, Pedestal	24	EA		
4.11	0646 1 60	Aluminum Signals Pole, Remove	15	EA		

BID ITEM	FDOT ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE RATE	ESTIMATED AMOUNT
Signalization (continued)						
4.12	0649 21 10	Steel Mast Arm Assembly, Furnish and Install, Single Arm 60', Valmont	1	EA		
4.13	0649 21 15	Steel Mast Arm Assembly, Furnish and Install, Single Arm 78', Valmont	2	EA		
4.14	0650 1 14	Vehicular Traffic Signal, Furnish & Install, Aluminum, 3 Section, 1 Way	6	EA		
4.14	0650 1 16	Traffic Signal, Furnish & Install Aluminum, 4 Section, 1 Way	2	EA		
4.15	0653 1 11	Pedestrian Signal, Furnish & Install Led Countdown, 1 Way	40	EA		
4.16	0653 1 12	Pedestrian Signal, Furnish & Install Led Countdown, 2 Ways	1	EA		
4.17	0653 1 60	Pedestrian Signal, Remove Ped Signal- Pole/Pedestal To Remain	31	EA		
4.18	0660 4 41	Vehicle Detection System- Video, Relocate Cabinet Equipment	3	EA		
4.19	0660 4 42	Vehicle Detection System- Video, Relocate Above Ground Equipment	3	EA		
4.20	0660 4 51	Vehicle Detection System- Video, Adjust Modify Cabinet Equipment	2	EA		
4.21	0665 1 12	Pedestrian Detector, Furnish and Install, Accessible	36	EA		
4.22	0665 1 60	Pedestrian Detector, Remove – Pole/Pedestal to Remain	31	EA		
4.23	0660 4 42	Internally Illuminated Sign, F&I, Overhead Mount, 12-18 SF	3	EA		
Pavement Markings						
5.01	0711 11102	Thermoplastic, Standard, White, Solid, 8 For Interchange and Urban Island	0.28	GM		
5.02	0711 11123	Thermoplastic, Standard, White, Solid, 12 For Crosswalk and Roundabout	5545	LF		
5.03	0711 11124	Thermoplastic, Standard, White, Solid, 18 For Diagonals And Chevrons	714	LF		
5.04	0711 11125	Thermoplastic, Standard, White, Solid, 24 For Stop Line And Crosswalk	1695	LF		

BID ITEM	FDOT ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE RATE	ESTIMATED AMOUNT
Pavement Markings (continued)						
5.05	0711 11141	Thermoplastic, Standard, White, 2-4 Dotted Guideline/ 6-10 Gap Extension, 6"	2.88	GM		
5.07	0711 11170	Thermoplastic, Standard, White, Arrow	241	EA		
5.06	0711 11160	Thermoplastic, Standard, White, Message Or Symbol	118 24	EA		
5.08	0711 11224	Thermoplastic, Standard, Yellow, Solid, 18 For Diagonal Or Chevrons	200	LF		
5.09	0711 11241	Thermoplastic, Standard, Yellow, 2-4 Dotted Guide Line /6-10 Dotted Extension Line, 6"	0.16	GM		
5.10	0711 15101	Thermoplastic, Standard - Open Graded Asphalt Surfaces, White, Solid, 6	16.45	GM		
5.11	0711 15102	Thermoplastic, Standard - Open Graded Asphalt Surfaces, White, Solid, 8	0.19	GM		
5.12	0711 15131	Thermoplastic, Standard-Open Graded Asphalt Surfaces, White, Skip, 6",10-30 Skip Or 3-9 Lane Drop	5.70	GM		
5.13	0711 15171	Thermoplastic, Standard-Open Graded Asphalt Surfaces, White, 6", 6-10 Dotted Managed Lane Marking	0.44	GM		
5.14	0711 15201	Thermoplastic, Standard - Open Graded Asphalt Surfaces, Yellow, Solid, 6"	5.84	GM		
5.15	706 1 3	Raised Pavement Marker, Type B - Per Plans and Details	1	LS		
5.16	0700 1 50	Single Post Sign, Relocate (Weston Style Sign)	5	EA		
5.17	0700 1 60	Single Post Sign, Remove (Weston style sign)	23	EA		
5.18	0700 1 11	Single Post Sign, F&I, Ground Mount Up to 12 SF	29	EA		
5.19	0700 1 12	Single Post Sign, F&I, Ground Mount 12-20 SF	1	EA		
5.20	0714 10	Green colored pavement markings	7413	SF		
5.21		Bike Lane Symbols (Green Pavement Marking, Helmeted Bicyclist, and Arrow Per BCTED)	94	EA		

BID ITEM	FDOT ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE RATE	ESTIMATED AMOUNT
Electrical						
6.01	0635 2 11	Pull & Splice Box, F&I, 13" X 24" Cover Size	14	EA		
6.02	0715 11213	Luminaire, F&I- Replace Existing Luminaire on Existing Pole/Arm, Roadway, Pole Top	17 15	EA		
6.03	0715 61121	Light Pole Complete, F&I, Standard Pole Standard Foundation, 35' Mounting Height, 10' Arm, Valmont	14 6	EA		
6.04	0715 5 32	Luminaire, F&I New Luminaire on New Mast Arm, Roadway, Pole top	3	EA		
6.05	0630 2 11	Conduit, Furnish and Install, Open Trench, Bus Shelter	300 80	LF		
6.06	0630 2 12	Conduit, Furnish and Install Directional Bore	2570 3177	LF		
6.07	715 69 220	Light Pole Complete Remove, Wiring, Conduit, Pull Box	6	EA		
6.08	715 1 11	Lighting Conductors, F&I, Insulated, No. 10 or <	336	LF		
6.09	715 1 12	Lighting Conductors, F&I, Insulated, No. 8 to 6	2485	LF		
6.10	715 1 13	Lighting Conductors, F&I, Insulated, No. 4 to 2	7758	LF		
6.11	751 2 1	F&I 10' x 5/8" Ground Rod, Cadweld	16	EA		
6.12	751 2 2	F&I Bus Shelter Transformer, Rack, Fuses, NEMA 3R Boxes	2	EA		
6.13	751 35 11	Bus Shelter Lights	4	EA		
Decorative Items – Not in Surtax Funding						
7.01	526-1-1	Weston style paver detectable warnings	84	SY		
7.02		Increase in cost for using City of Weston Standard Sign Posts. This cost is in addition to the cost of Pay Item 5.18, F&I (Up to 12 SF)	29	EA		
7.03		Increase in cost for using City of Weston Standard Sign Posts. This cost is in addition to the cost of Pay Item 5.19, F&I (12 to 20 SF)	1	EA		
Miscellaneous						
8.01		Contingency – to be used at the City's discretion	1	LS	\$100,000.00	\$100,000.00

Grand Total (Figures)	\$
------------------------------	-----------

Grand Total (Written in words)

Name of CONTRACTOR (Please Print)

Signature	Title	Date
------------------	--------------	-------------

SECTION 01012

REVISED MEASUREMENT AND PAYMENT

1.01 DESCRIPTION

- A. This Section includes administrative and procedural requirements for determining payment for Work completed that is not covered by FDOT pay items and corresponding Basis of Estimates.
- B.

1.02 PROTECTION

- A. Where pavement, pipes, valves, appurtenances, trees, shrubbery, fences, other property or structures are in proximity to the Work, adequate protection shall be provided. Such protection is considered incidental to construction and shall not be assigned as a separate pay item.

1.03 RESTORATION

- A. Where pavement, pipes, valves, structures, appurtenances, trees, shrubbery, fences, other property or structures not designated as pay items, have been damaged, removed or disturbed by the Contractor, whether deliberately or through failure to carry out the requirements of the Contract Documents, state laws, municipal ordinances or the specific direction of the Engineer, or through failure to employ usual and reasonable safeguards, such property and surface structures shall be replaced or repaired at the expense of the Contractor to a condition equal to that before Work began within a time frame approved by the Engineer. Such restoration is considered incidental to construction and shall not be assigned as a separate pay item.
- B. Any damage to existing sidewalk, asphalt, sod, concrete, or other surface outside of the limits shown and quantified in the bid form and in the Drawings shall be replaced at the Contractor's expense at no additional cost to the Town.

1.04 EXPLORATORY EXCAVATIONS

- A. The Contractor shall verify the exact locations and depths of all utilities shown and shall conduct exploratory excavations of all utilities that may interfere with the Work. All such exploratory excavations shall be performed as soon as practicable after award of the Contract and, in any event, enough time in advance of construction to avoid possible delays to the Contractor's work. When such exploratory excavations show the utility location as shown to be in error, the Contractor shall so notify the Engineer. The cost for conducting these excavations shall be considered incidental to construction and shall not be assigned as a separate pay item.

1.05 TESTING, SURVEY, AND RECORD DRAWINGS

- A. All survey layout and record drawings shall be considered incidental to the cost of construction and shall include all calculations and field work required, in order to establish all horizontal and vertical controls, set all stakes needed, such as grade stakes, offset stakes, reference point stakes, slopes stakes, and other reference marks or points necessary to provide lines and grades for construction and as-building of all roadway, utility construction, and miscellaneous items.
- B. All testing shall be considered incidental to the cost of construction, shall not be assigned as a separate pay item, and shall include all field testing and laboratory work including reports as required by the Drawings and specifications and by agencies having jurisdiction over the project.

PART 2 - PRODUCTS (NOT APPLICABLE)

PART 3 - EXECUTION - PHASE ONE BID ONLY

GENERAL

3.01 MOBILIZATION AND DEMOBILIZATION - BID ITEM NO. 1.01

- A. Payment shall be made as a percentage of the Lump Sum Price.
- B. The Lump Sum Price shall include compensation for all labor, materials, equipment, and all other incidentals required for all temporary facilities, transportation, communications, office, maintenance, project signs, and any other pre- or post-construction expenses necessary for the start or cessation of the Work, not specifically identified in the costs of the Work.
- C. No further payment shall be made for remobilization unless all the Work is suspended by the Owner for a period more than three months and through no fault to the Contractor.
- D. The Lump Sum price shall include cleaning and desilting the existing drainage including at least two existing structures upstream and all downstream of any connections to the existing system.
- E. The Lump Sum Price shall not exceed five percent (5%) of the total contract price.

3.02 MAINTENANCE OF TRAFFIC - BID ITEM NO. 1.02

- A. Payment shall be made as a percentage of the Lump Sum Price.
- B. The Lump Sum Price shall include compensation for required labor, materials, all necessary temporary pavement markings and signing for vehicles, bicyclists, and pedestrians, temporary pavement, temporary business signage, professional fees, and equipment necessary to provide traffic control for two-way traffic at all times in accordance with the plans and specifications.

- C. MOT permits and approvals from the applicable regulatory agencies, including but not limited to City of Weston, Broward County Traffic Engineering Division and the FDOT, are the responsibility of the Contractor. MOT shall include both vehicular and pedestrian requirements.
- D. Temporary pavement markings and signage shall be provided wherever existing has been damaged, removed, or is no longer visible. The temporary shall be maintained until final markings are installed after asphalt resurfacing.
- E. The cost of two variable message signs installed at least 2 weeks in advance of construction shall be included in the lump sum price.
- F. The Lump Sum Price shall not exceed five percent (5%) of the total contract price.

3.03 STORMWATER POLLUTION PREVENTION - BID ITEM NO. 1.03

- A. Payment shall be made as a percentage of the Lump Sum Price.
- B. The Lump Sum Price shall include full compensation for all equipment, materials, supplies, and labor necessary to prepare, obtain permit approval from the governing agency, and implement the prevention, control, and abatement of erosion and water pollution. Work shall include but not be limited to mulching, sand bagging, slope drains, sediment basins, silt dike, berms, baled hay or straw, silt fences and staked turbidity barriers, rock bags, artificial coverings and other items relating to the construction/removal and routine maintenance, including mowing, or implementing the Stormwater Pollution Prevention Plan.

3.04 PERMITTING/MISC. WORK ALLOWANCE - BID ITEM NO. 1.04

- A. Payment for permitting allowance will be based on the actual permit, license or fee paid directly to the agency, documented by paid receipts, specifically excluding any labor, mark-up, overhead and profit, administration and other costs involved in obtaining permits or licenses or paying fees. The Contractor is responsible for submitting and obtaining all necessary regulatory agency permits other than those provided by the Owner or the Engineer, and the Contractor is responsible for paying for all associated permit fees which are specifically excluded from this allowance and to be included in the various bid items herein. Fees specifically excluded from this allowance, include, but are not limited to: reinspection fees, expired permit fees stand by time, failed test and bacteriological testing fees. Only permit fees substantiated by the Contractor and approved by the Owner and Engineer will be paid as part of this Item. Any balance in this bid item at the end of the project shall be credited back to the Owner.
- B. Payment for the miscellaneous work allowance shall be full compensation for additional items of Work requested by the Town or warranted unforeseen conditions found during construction and approved by the Town. The Contractor is required to provide a quote with unit price breakdowns of the Work to the Town for review and approval prior to commencing any Work. These allowances are for the sole use and discretion by the Town to cover unforeseen or unanticipated costs. The cost of these allowances is not guaranteed to be used and compensated to the Contractor in part or in whole if the Town does not require their use.

- C. Any balance in these bid items at the end of the project shall be credited back to the Owner.

3.05 GENERAL REQUIREMENTS - BID ITEM NO. 1.05

- A. Payment shall be made as a percentage of the Lump Sum Price.
- B. The Lump Sum Price shall include the cost of bonds, insurance, licenses, and all other costs not specifically identified in other bid items. This Lump Sum price shall also include the cost for the Payment and Performance Bonds and a copy of the payment receipt must be provided for reimbursement.
- C. The Lump Sum Price shall exclude the cost of construction material and installation.
- D. The Lump Sum Price shall not exceed ten percent (10%) of the total contract price.

3.06 CLEARING AND GRUBBING – BID ITEM 3.01

- A. Pay Item 110-1- shall also include the removal of existing pipes were excavation will be done, or where embankment or structures will be constructed. It also includes grouting and abandoning pipe as noted in the plans.

3.07 RELOCATE/RECONSTRUCT EXISTING BUS SHELTER – BID ITEM NO. 3.21

- A. Pay item 751-35-43 shall also include compensation for all labor, material, and equipment required to remove and relay existing pavers, removing the existing foundation, pouring a new foundation, relocating bike rack and trash can, and relocating the associated signage. The price shall also include removing any retaining wall, and includes removal of the existing electrical service, existing associated equipment, existing conduit and wiring, and lights for the existing shelter. The new electrical service and components and the lighting for the shelters are paid under separate pay items.

3.08 IRRIGATION SYSTEM MODIFICATIONS - BID ITEM NO. 3.23

- A. Payment for this item shall be made as a percentage of the lump sum price.
- B. The Contractor's Lump Sum Cost shall also include full compensation for all labor, equipment, materials, restoration and installation required for the Modifications to the Existing Irrigation System including, but not limited to, as-built documentation of the existing irrigation system and provide all modifications necessary to a portion of the existing system, as required, to accommodate the improvements to the roadway and drainage within the project limits, as indicated in the plans, details, and specifications.
- C. The Contractor's Lump Sum Cost shall also include the complete restoration of the surface disturbed by the irrigation demolition and installation including but not limited to pavement restoration, sidewalk restoration, and landscape restoration, etc.

3.09 BIKE LANE SYMBOLS BID ITEM NO. 5.21

- A. Payment for this item shall include furnishing and installing the thermoplastic Green colored pavement with the white thermoplastic helmeted bicyclist and the white thermoplastic arrow per the plans. The installation and material shall follow Broward County Traffic Engineering Bicycle Pavement Markings and Signs Details.
- B. Payment for the green pavement marking filling the area between the 6" white 2'-4' skips shall be included in the bid item 5.20.

3.10 ADDITIONAL PAY ITEM NOTES CAN BE FOUND ON SHEET T-9.