

ADDENDUM NO. 1

BID TITLE: Weston North Walking Nature Trail

BID NO: 2025-04

DATE: July 31, 2025

To All Bidders:

Bidders for the above referenced BID shall take note of the following changes, additions, deletions, clarifications, etc., to the BID documents, which shall become a part of and have precedence over anything shown or described otherwise.

A. CHANGES IN THE BID DOCUMENTS

- 1) ARTICLE 7, BID AMOUNTS, is hereby being replaced with the attached REVISED ARTICLE 7, BID AMOUNTS.

B. CLARIFICATIONS

None.

C. QUESTIONS FROM BIDDERS

- 1) Q: In refence this bid there is a discrepancy between plans and article 7 Bid Amounts. In the plans and specs talk about "Coquina mortar" as final surface but in the Bid Amounts talks about Washed pea rock (# 4).

A: See attached REVISED ARTICLE 7, BID AMOUNTS.

ATTACHMENTS

- 1) REVISED ARTICLE 7, BID AMOUNTS

END OF ADDENDUM NO. 1

All other information remains as originally described in the solicitation.

REVISED ARTICLE 7.0
BID AMOUNTS

The Bidder offers the following for providing all labor, supervision, equipment, supplies, tools, safety measures and all other necessary incidentals to complete the project in accordance with the contract documents (project manual and plans). The lump sum costs for each individual portion of the Work as set out herein shall be inclusive of all costs for each.

Bid Item	Description of Item	UOM	Qty	Unit Cost	Ext. Cost
1	Mobilization (Max. 2% of Project Cost)	LS	1	\$ _____	\$ _____
2	Clearing & Grubbing - Grading, Removal & Disposal of Materials, Leveling and Site Preparation	SF	82,000	\$ _____	\$ _____
3	Furnish & Install 4-Inch Heavy Duty/Commercial Grade Polyethylene Landscape Edging Border with Non-Rust Stakes	LF	18,500	\$ _____	\$ _____
4	Furnish & Install 5-Inch Thick, 6 feet Wide Coquina/Mortar Mix (4:1) Aggregate, Graded & Compacted	SF	56,000	\$ _____	\$ _____
5	Furnish & Install 6" Limerock Base (LBR 100)	SF	75,000	\$ _____	\$ _____
6	Furnish & Install 15' X 20' Stabilized Sod Ramp	LS	1	\$ _____	\$ _____
7	Furnish & Install 12" Clean Fill, Grade & Compact	CY	500	\$ _____	\$ _____
8	Furnish & Install 6" HDPE Pipe & Fittings	LF	70	\$ _____	\$ _____
9	Root Pruning	LS	1	\$ _____	\$ _____
10	Furnish & Install Kompan Dip Bench Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
11	Furnish & Install Kompan Sit Up Bench Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
12	Furnish & Install Kompan Multi Timer Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
13	Furnish & Install Kompan Hurdles Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____

Bid Item	Description of Item	UOM	Qty	Unit Cost	Ext. Cost
14	Furnish & Install Kompan Balance Beam Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
15	Furnish & Install 32 Gallon, 30"X35" Powder Coated Garbage Receptacle on Concrete Pad	EA	3	\$ _____	\$ _____
16	Furnish & Install Bahia Sod	SF	56,000	\$ _____	\$ _____
17	Wayfinding Signage Allowance	LS	1	\$15,000.00	\$15,000.00
18	Owner's Contingency	LS	1	\$25,000.00	\$25,000.00
Grand Total (Bid Items 1 through 18):					\$ _____

Grand Total (Written in words)

Name of CONTRACTOR (Please Print)

Signature

Title

Date