

## ADDENDUM NO. 2

BID TITLE: Weston North Walking Nature Trail

BID NO: 2025-04

DATE: August 11, 2025

To All Bidders:

Bidders for the above referenced Bid shall take note of the following changes, additions, deletions, clarifications, etc., to the Bid documents, which shall become a part of and have precedence over anything shown or described otherwise.

### A. CHANGES IN THE BID DOCUMENTS

- 1) The description for Bid Item No. 4 has been changed to read: *"Furnish & Install **4-Inch** Thick, 6 feet Wide Coquina/Mortar Mix (4:1) Aggregate, Graded & Compacted"*. See REVISED ARTICLE 7.0, BID AMOUNTS, enclosed herewith.
- 2) Document 0010-01 NOTICE TO BIDDERS; the project site location has been revised to read as follows:

Bids shall be accepted from qualified, experienced and licensed general contractors to furnish all labor, supervision, equipment, supplies, tools, permitting, safety measures and all other necessary incidentals to construct an off-road unpaved walking nature trail on CITY property along landscaping berm areas. **The project site runs parallel to SR 84, east of Indian Trace to the Bonaventure Canal, then south along the canal bank, ending north of Saddle Club Road.** The project consists of the removal and disposal of shrubs, trees, roots, etc. and the constriction of approximately 9,200 linear feet of unpaved walking trail, wayfinding signage, safety signage and other amenities.

### B. CLARIFICATIONS

None.

### C. QUESTIONS FROM BIDDERS

- 1) Q: What is the estimated budget?  
A: Estimated budget is \$700,000
- 2) Q: SIT UP BENCH, MULTI TIMER, HURDLES, DIP BENCH, BALANCE BEAM (ROBINIA) are not included in the Bid Amounts Form, Article 7.0  
A: See Addendum No. 1 for clarification.
- 3) Q: What is the anticipated start date?  
A: Expected to commence October 2025.

- 4) Q: There is still a difference between plans and bid amounts over #4 item "Coquina Mortar". The plans ask for 4" thick mortar and the bid amounts ask for 5" of mortar. As bid amounts show SF there is a big difference in price from 4" to 5" thick. Which one is the correct thick of mortar?

A: The project requires 4" thick coquina mortar mix. See Section A, CHANGES TO DOCUMENT, as noted herein.

- 5) Q: Will the CITY, or engineer, be accepting alternatives or VE options in lieu of the 4" Coquina/ Mortar (4:1) Mix for the trail surface on this job? We would be interested in quoting/submitting a flexible porous pavement of the option would be entertained.

A: No, the requirement for the project is to have a natural trail surface. Synthetic material cannot be used.

- 6) Q: There is no line item for storm water measures. Successful Contractor is to submit SWPPP plan. Should there be a storm water measures allowance line item be added for the bid submission?

A: SWPPP is incidental to the project and the cost shall be incorporated into the listed bid line items.

#### ATTACHMENTS

- 1) Non-Mandatory Virtual Pre-Proposal Conference Attendance Log
- 2) REVISED ARTICLE 7.0, BID AMOUNTS

**END OF ADDENDUM NO. 2**  
**All other information remains as originally described in the solicitation**

**NON-MANDATORY VIRTUAL PRE-PROPOSAL CONFERENCE  
ATTENDANCE LOG  
Bid No. 2025-04  
Weston North Walking Nature Trail  
Date: August 4, 2025 at 11:00 a.m.**

	<b>First Name</b>	<b>Last Name</b>	<b>Company</b>	<b>Email Address</b>
1	Fidel	Maceda	Maceda Contractors LLC	macedagc@att.net
2	Waldy	Polizzi	Westwind Contracting, Inc.	waldyp@westwindcontracting.com
3	Mehrdad	Mahmoudi		mehrdadorama@gmail.com
4	Michael	Kalman	XGD Systems, LLC	mkalman@xgd.systems.com
5	Tom	Koch	MBR Construction	tkoch@mbrconstruction.com
6	Cesar	De Luna	M&J Construction Group	cesar@mjgeneralcontractors.com
7	Javier	Gonzales	Westwind Contracting, Inc.	Call-In User
8	Benny	Bejar	Bejar Construction, Inc.	Call-In User
9	Ava	Fernandez	Waypoint Contracting	afernandez@waypointci.com
10	Llasbell	Piantini	American Design Engineering Construction	llasbell.piantini@adeconstructioninc.com
11	Carson	McQueen	Ranger Rubber, LLC	cmcqueen@rangerrubber.com

**REVISED - ARTICLE 7.0**  
**BID AMOUNTS**

The Bidder offers the following for providing all labor, supervision, equipment, supplies, tools, safety measures and all other necessary incidentals to complete the project in accordance with the contract documents (project manual and plans). The lump sum costs for each individual portion of the Work as set out herein shall be inclusive of all costs for each.

Bid Item	Description of Item	UOM	Qty	Unit Cost	Ext. Cost
1	Mobilization (Max. 2% of Project Cost)	LS	1	\$ _____	\$ _____
2	Clearing & Grubbing - Grading, Removal & Disposal of Materials, Leveling and Site Preparation	SF	82,000	\$ _____	\$ _____
3	Furnish & Install 4-Inch Heavy Duty/Commercial Grade Polyethylene Landscape Edging Border with Non-Rust Stakes	LF	18,500	\$ _____	\$ _____
4	Furnish & Install <u>4-Inch</u> Thick, 6 feet Wide Coquina/Mortar Mix (4:1) Aggregate, Graded & Compacted	SF	56,000	\$ _____	\$ _____
5	Furnish & Install 6" Limerock Base (LBR 100)	SF	75,000	\$ _____	\$ _____
6	Furnish & Install 15' X 20' Stabilized Sod Ramp	LS	1	\$ _____	\$ _____
7	Furnish & Install 12" Clean Fill, Grade & Compact	CY	500	\$ _____	\$ _____
8	Furnish & Install 6" HDPE Pipe & Fittings	LF	70	\$ _____	\$ _____
9	Root Pruning	LS	1	\$ _____	\$ _____
10	Furnish & Install Kompan Dip Bench Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
11	Furnish & Install Kompan Sit Up Bench Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
12	Furnish & Install Kompan Multi Timer Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
13	Furnish & Install Kompan Hurdles Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____

Bid Item	Description of Item	UOM	Qty	Unit Cost	Ext. Cost
14	Furnish & Install Kompan Balance Beam Robinia or Approved Equal Exercise Station and Equipment	EA	2	\$ _____	\$ _____
15	Furnish & Install 32 Gallon, 30"X35" Powder Coated Garbage Receptacle on Concrete Pad	EA	3	\$ _____	\$ _____
16	Furnish & Install Bahia Sod	SF	56,000	\$ _____	\$ _____
17	Wayfinding Signage Allowance	LS	1	\$15,000.00	\$15,000.00
18	Owner's Contingency	LS	1	\$25,000.00	\$25,000.00
<b>Grand Total (Bid Items 1 through 18):</b>					\$ _____

---

Grand Total (Written in words)

---

Name of CONTRACTOR (Please Print)

---

Signature

Title

Date